


NOZZLE SCHEDULE			
MARK	QTY	SIZE / RATING	DESCRIPTION
N1	1	2" 3000# NPT	INLET
N2	1	2" 3000# NPT	OUTLET
N3	2	1/2" 3000# NPT	PRESSURE GAUGE
N4	1	1/2" 3000# NPT	VENT
N5	1	1" 3000# NPT	CLEAN DRAIN
N6	1	1" 3000# NPT	DIRTY DRAIN

VESSEL DESIGN CONDITIONS	
CODE:	ASME SECTION VIII DIV. 1, 2015 EDITION
M.A.W.P.:	150 PSI @ 400°F
M.D.M.T.:	-20° F @ 150 PSI
M.A.W.P.:	FV PSI @ 400°F
CORROSION ALLOWANCE:	NONE
HYDROTEST PRESS:	195 PSI
STAMP:	UM
SERVICE:	NON LETHAL
PWHT:	N/A
RADIOGRAPHY:	N/A
MATERIAL:	SS316
GASKET:	BUNA

- NOTES:
- DRY WEIGHT: 48.09 LBS
  - FLOODED WEIGHT: 100 LBS
  - SHIPPING WEIGHT: 120 LBS
  - VESSEL VOLUME: 0.4 FT<sup>3</sup>
  - VESSEL WILL HOUSE (QTY=1) 2.5" OD x 30" LG CARTRIDGE



APPROVED WITH MARK-UPS  APPROVED

<p>THIRD ANGLE PROJECTION</p>	<p><b>FIL-TREK CORPORATION</b></p>	
	<p>55 Stafford Court Cambridge, Ontario N1T 1B3 Canada</p>	<p>Phone: (519) 623-7448 Fax: (519) 623-8807 Email: info@fil-trek.com Website: www.fil-trek.com</p>
<p>THIS DRAWING IS THE PROPERTY OF 'FIL-TREK CORPORATION' AND MUST NOT BE COPIED OR USED IN ANY WAY DETRIMENTAL TO THE CORPORATION</p>		
<p>EQUIPMENT: GL SERIES (CARTRIDGE FILTER VESSEL)</p>		
<p>MODEL NO: S6GL04-001-3-2P-150</p>		
<p>CUSTOMER:</p>		
<p>PARENT: NEW DESIGN</p>	<p>DRAWN: JN</p>	<p>DATE: 07/06/2017</p>
<p>CHK'D:</p>	<p>SCALE: NTS</p>	<p>SERIAL No. Part No. 001001-00343</p>
		<p>REV. No. 0</p>