


SECTION U-U
SCALE 1 : 12

NOZZLE SCHEDULE			
MARK	QTY	SIZE / RATING	DESCRIPTION
N1	1	4" RF50 CL150	INLET
N2	1	4" RF50 CL150	OUTLET
N3	2	1/2" NPT CL3000	PRESSURE GAUGE
N4	1	1/2" NPT CL3000	VENT
N5	1	1/2" NPT CL3000	CLEAN DRAIN
N6	0		DIRTY DRAIN
VESSEL DESIGN CONDITIONS			
CODE: ASME SECTION VIII DIV. 1, 2019 EDITION			
M.A.W.P.: 150 PSI @ 400°F		M.D.M.T.: -20°F @ 150 PSI	
M.A.W.P.: FV PSI @ 400°F		HYDROTEST PRESS: 195 PSI	
CORROSION ALLOWANCE: N/A		SERVICE: UNK. LIQUID, NON-LETHAL	
STAMP: UM		RADIOGRAPHY: N/A	
PWHT: N/A		GASKET: ☐ BUNA ☐ VITON ☐ EPDM ☐ OTHER: _____	
MATERIAL: SS316			
NOTES: DRY WEIGHT: 140 LBS SHIPPING WEIGHT: 170 LBS VOLUME: 0.75 CU. FT. INTERNALS: 1 X SIZE 1 BAKSET		FACTORY INSTALLED OPTIONS:	
		☐ STAINLESS STEEL BOLTING (SS316)	
		☐ MESH LINED BASKETS: _____ MESH	
		☐ N3 DIFFERENTIAL PRESSURE GAUGE TYPE: _____	
		☐ N4 PRESSURE RELIEF VALVE TYPE: _____	
		☐ N4 AIR ELIMINATOR TYPE: _____	
		☐ N4 VENT VALVE	
		☐ N5/N6 DRAIN VALVES	



APPROVED WITH MARK-UPS



TOLERANCES-UNLESS OTHERWISE NOTED	
DECIMAL	.X = $\pm 1^\circ$.XX = $\pm .02^\circ$.XXX = $\pm .005^\circ$
FRACTIONAL	$\pm 1/8^\circ$
ANGULAR	$\pm 1^\circ$
MAX. MACHINED SURFACE FINISH	125 \

**FIL-TREK CORPORATION**

55 Stafford Court
Cambridge, Ontario
N1T 1B3
Canada

Phone: (519) 623-7448
Fax: (519) 623-8807
Email: info@fil-trek.com
Website: www.fil-trek.com

THIS DRAWING IS THE PROPERTY OF 'FIL-TREK CORPORATION' AND MUST NOT BE COPIED OR USED IN ANY WAY DETRIMENTAL TO THE CORPORATION

EQUIPMENT:	SL SERIES (BAG FILTER HOUSING)
------------	--------------------------------

MODEL NO:	S6SL111-4F-A-150
-----------	------------------

CUSTOMER:

VESSEL
QUANTITY:

DRAWN: CL

DATE:
2020-03-05

SERIAL No.	
------------	--

Part No.	
----------	--

REV. No.

0