


SECTION U-U
SCALE 1 : 12

NOZZLE SCHEDULE			
MARK	QTY	SIZE / RATING	DESCRIPTION
N1	1	2" RFSO CL150	INLET
N2	1	2" RFSO CL150	OUTLET
N3	2	1/2" NPT CL3000	PRESSURE GAUGE
N4	1	1/2" NPT CL3000	VENT
N5	1	1/2" NPT CL3000	CLEAN DRAIN
N6	0		DIRTY DRAIN
VESSEL DESIGN CONDITIONS			
CODE: ASME SECTION VIII DIV. 1, 2019 EDITION			
M.A.W.P.: 150 PSI @ 400°F		M.D.M.T.: -20°F @ 150 PSI	
M.A.W.P.: FV PSI @ 400°F		HYDROTEST PRESS: 195 PSI	
CORROSION ALLOWANCE: N/A		SERVICE: UNK. LIQUID, NON-LETHAL	
STAMP: UM		RADIOGRAPHY: N/A	
PWHT: N/A		GASKET: ☐ BUNA ☐ VITON ☐ EPDM ☐ OTHER: _____	
MATERIAL: CS			
NOTES: DRY WEIGHT: 150 LBS SHIPPING WEIGHT: 180 LBS VOLUME: 1 CU. FT. INTERNALS: 1 X SIZE 2 BAKSET		FACTORY INSTALLED OPTIONS:	
		☐ STAINLESS STEEL BOLTING (SS316)	
		☐ MESH LINED BASKETS: _____ MESH	
		☐ N3 DIFFERENTIAL PRESSURE GAUGE TYPE: _____	
		☐ N4 PRESSURE RELIEF VALVE TYPE: _____	
		☐ N4 AIR ELIMINATOR TYPE: _____	
		☐ N4 VENT VALVE	
		☐ N5/N6 DRAIN VALVES	



APPROVED WITH MARK-UPS

APPROVED ☐



TOLERANCES-UNLESS OTHERWISE NOTED	
DECIMAL	.X = $\pm 1^\circ$.XX = $\pm 0.02^\circ$.XXX = $\pm 0.005^\circ$
FRACTIONAL	$\pm 1/8^\circ$
ANGULAR	$\pm 1^\circ$
MAX. MACHINED SURFACE FINISH	125 μ

**FIL-TREK CORPORATION**

55 Stafford Court
Cambridge, Ontario
N1T 1B3
Canada

Phone: (519) 623-7448
Fax: (519) 623-8807
Email: info@fil-trek.com
Website: www.fil-trek.com

THIS DRAWING IS THE PROPERTY OF 'FIL-TREK CORPORATION' AND MUST NOT BE COPIED OR USED
IN ANY WAY DETRIMENTAL TO THE CORPORATION

EQUIPMENT:	SL SERIES (BAG FILTER HOUSING)
------------	--------------------------------

MODEL NO:	SL112-2F-DB-150
-----------	-----------------

CUSTOMER:

VESSEL
QUANTITY:

DRAWN: CL
CLINIC: A3

DATE:	2020-03-05
SCALE:	1:100

SERIAL N

Part No.	002002-00706
----------	--------------

REV. No.	0
----------	---