



SECTION K-K  
SCALE 1 : 14

#### NOZZLE SCHEDULE

| MARK | QTY | SIZE / RATING   | DESCRIPTION    |
|------|-----|-----------------|----------------|
| N1   | 1   | 3" RF SO CL150  | INLET          |
| N2   | 1   | 3" RF SO CL150  | OUTLET         |
| N3   | 2   | 1/2" NPT CL3000 | PRESSURE GAUGE |
| N4   | 1   | 1/2" NPT CL3000 | VENT           |
| N5   | 1   | 1/2" NPT CL3000 | CLEAN DRAIN    |
| N6   | 1   | 1/2" NPT CL3000 | DIRTY DRAIN    |

#### VESSEL DESIGN CONDITIONS

|                      |                          |                                 |                                                                                            |
|----------------------|--------------------------|---------------------------------|--------------------------------------------------------------------------------------------|
| CODE:                | BEST COMMERCIAL PRACTICE |                                 |                                                                                            |
| M.A.W.P.:            | 150 PSI @ 250°F          | M.D.M.T.:                       | -20°F @ 150 PSI                                                                            |
| M.A.W.P.:            | FV PSI @ 250°F           | HYDROTEST PRESS:                | 195 PSI                                                                                    |
| CORROSION ALLOWANCE: | N/A                      | SERVICE:                        | UNK. LIQUID, NON-LETHAL                                                                    |
| STAMP:               | N/A                      | RADIOGRAPHY:                    | N/A                                                                                        |
| PWHT:                | N/A                      | GASKET:                         | <input type="checkbox"/> BUNA <input type="checkbox"/> VITON <input type="checkbox"/> EPDM |
| MATERIAL:            | SS316                    | <input type="checkbox"/> OTHER: |                                                                                            |

**NOTES:**  
 DRY WEIGHT: 240 LBS  
 SHIPPING WEIGHT: 280 LBS  
 VOLUME: 2.8 CU. FT.  
 INTERNALS: 10 x 2.5" OD FILTER CARTRIDGES

**FACTORY INSTALLED OPTIONS:**  
☐ STAINLESS STEEL BOLTING (SS316)  
☐ N3 DIFFERENTIAL PRESSURE GAUGE TYPE: \_\_\_\_\_  
☐ N4 PRESSURE RELIEF VALVE TYPE: \_\_\_\_\_  
☐ N4 AIR ELIMINATOR TYPE: \_\_\_\_\_  
☐ N4 VENT VALVE  
☐ N5/N6 DRAIN VALVES



APPROVED WITH MARK-UPS ☐ APPROVED ☐



THIRD ANGLE PROJECTION  
 TOLERANCES-UNLESS OTHERWISE NOTED  
 DECIMAL .X = ±.1"  
 .XX = ±.02"  
 .XXX = ±.005"  
 FRACTIONAL = ±1/8"  
 ANGULAR = ± 1°  
 MAX. MACHINED SURFACE FINISH 125/√



#### FIL-TREK CORPORATION

55 Stafford Court  
 Cambridge, Ontario  
 N1T 1B3  
 Canada

Phone: (519) 623-7448  
 Fax: (519) 623-8807  
 Email: info@fil-trek.com  
 Website: www.fil-trek.com

THIS DRAWING IS THE PROPERTY OF 'FIL-TREK CORPORATION' AND MUST NOT BE COPIED OR USED IN ANY WAY DETRIMENTAL TO THE CORPORATION

EQUIPMENT: GL SERIES (CARTRIDGE FILTER VESSEL)

MODEL NO: S6EGL10-010-4-3F-A-150

CUSTOMER:

VESSEL QUANTITY:

DRAWN: CL  
 CHK'D: AJ

DATE: 2021-01-05  
 SCALE: NTS

SERIAL No.

Part No. 001022-00752

REV. No. 0